9. The wood in the stacking place must be at the risk of a contractor until it is stacked, measured and accepted by the Superintending Engineer or his representatives. The stacks will be measured thirty days after they are built allowing sufficient time for the fuel to dry.

10. When stacks are taken over the contractor or his representative must be present during the time of the measurement and must sign the record of measurement in token of his agreement to the correctness thereof.

11. Soft wood unsuitable for steaming purposes will not be accepted.

12. Jali, Thipyala, Devadari, Chigari, Hunsai, Heddarns, and other equal hard wood than those specified above which the contractor would like to supply may be supplied after he has got the previous sanction of the Superintending Engineer or his representatives. A cart-load of such fuel is to be brought in first when the same will be tested and if suitable the contractor will be given permission in writing, to such wood also in addition to the list of wood already approved of.

13. The quantity of fuel to be supplied from the date of the signing the bond up to June 1916 is tons per month.

14. Should the contractor fail to supply the stipulated quantity of fuel in two consecutive months the Superintending Engineer or his representatives can order for collection by separate agency at the risk of the contractor or cancel his contract crediting the whole or a part of the reserved amount to Government.

15. A reserve of 5 per cent will be withheld from the contractor's bill up to Rs. 2,500 and it will be paid till the accounts are finally settled.

16. The Superintending Engineer or his representatives is at liberty to cut and stack fuel by other agency from the trees in tank bed and other Government trees within the area of the Cauvery Reservoir works.

B. B. GARUDACHARYA,
For *Superintending Engineer, Cauvery Reservior Works.*

MYSORE CITY IMPROVEMENT TRUST BOARD.

Dated 5th May 1916.

Notice is hereby given that sealed tenders will be received at the office of the Chairman, City Improvement Trust Board, Mysore, up to 19th June 1916, for constructing open surface drains with cement concrete in the Chamundi extension. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1917.

2. The plans, detailed estimate and conditions may be seen at the Chairman's Office at the Town Hall, Mysore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Chairman. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Statement of quantities for constructing open surface drains with cement concrete in Chamundi extension, Mysore.

No.	Items	Per	Quantity
	CONSTRUCTING CEMENT CONCRETE DRAINS.		
1	Earthwork excavation average soil	C. yd.	2,045
2	Cement concrete rendering the surface smooth with cement. (1 : 2½ : 5 field jelly).	C.ft.	26,190
3	Burnt stone covering slabs 5" to 6" thick dressed at sides and set in mortar ...	S. ft.	8,993
4	Burnt stone parapet 5" to 6" thick one line dressed and set in cement concrete including pointing.	,,	5,408

NOTE.—Cement will be supplied at a rate of Rs. 12 per barrel.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing open surface drains with cement concrete," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Government of Mysore, who do not bind themselves to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Chairman's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Dated 5th May 1916.

Notice is hereby given that sealed tenders will be received at the office of the Chairman, City Improvement Trust Board, Mysore, up to 19th June 1916, for diverting the Bennaharadanahalli feeder channel in the Chamundi extension. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1917.

2. The plans, detailed estimate and conditions may be seen at the Chairman's Office at the Town Hall, Mysore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Chairman. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

Statement of quantities for diverting the Bennaharadanahalli feeder channel in Chamundi extension.

No.	Items	Per	Quantity
1	Earthwork excavation and filling hollows, etc., average soil	C. yd.	1,623
2	Chunam mortar concrete	C. ft.	5,876
3	Burnt stone slabs 3" to 4" thick for bed	S. ft.	8,690
4	Sized stones with ordinary mortar	C. ft.	12,578
5	Covering slabs 6" thick dressed at sides and set in cement mortar	S. ft.	225
6	Pointing with cement mortar	Sqr.	122·56

NOTE.—Cement will be supplied at a rate of Rs. 12 per barrel.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for diverting the Bennaharadanahalli feeder channel in Chamundi extension," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Government of Mysore, who do not bind themselves to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Chairman's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

T. G. LAKSHMANA RAO,
Chairman.

MYSORE STATE TROOPS, BANGALORE.

Notice dated 20th April 1916.

1. Tenders are invited for the supply of the undermentioned article required for the Military Stores, Mysore Government, Bangalore.

2. Tenders should be in the undermentioned form, sealed and addressed to the Chief Commandant, Mysore State Troops, and superscribed "Tenders for the supply of new pattern Officer's swords as per specification noted below."

3. Tenders will be received at the Chief Commandant's Office till 2 P.M. on Thursday the 25th May 1916, after which no tender will be received.

4. Tenders should clearly show the rate at which the article (which should correspond with the sealed sample) can be supplied. The sealed sample of the article could be seen in the Mysore Government Military Stores on any day during office hours.

5. Every tender should be accompanied with a deposit of Rs. 50 in currency notes. If the tender is accepted and the tenderer fails to undertake the contract, he will forfeit the amount. If the tender is not accepted the amount will be returned to the tenderer.